



PROJECT NAME	The LEGO Group Istanbul Office Project	DATE	21.09.2026
LOCATION	Trump Tower	REV NO	1
Sqm (net)	720	€/sqm	€ 1.555,50

CONSTRUCTION WORKS

A	ARCHITECTURAL WORKS TOTAL	€ 672.310,29
B	ELECTRICAL WORKS TOTAL	€ 168.770,65
C	MECHANIC WORKS TOTAL	€ 197.151,33
D	LIGHTING WORKS TOTAL	€ 81.728,08

CONSTRUCTION WORKS GRAND TOTAL (VAT is excluded) € 1.119.960,35

OPTIONAL CONSTRUCTION WORKS TOTAL (VAT is excluded) € 2.063,28

E	OPTIONAL ARCHITECTURAL WORKS TOTAL	€ 153,68
F	OPTIONAL ELECTRICAL WORKS TOTAL	
G	OPTIONAL MECHANIC WORKS TOTAL	€ 1.909,60
H	OPTIONAL LIGHTING WORKS TOTAL	



PROJECT NAME	The LEGO Group Istanbul Office Project
LOCATION	Trump Tower
Sqm (net)	720

Architectural	GENERAL WORKS	€ 672.310,29	€ 85.594,92
	FLOOR WORKS		€ 96.630,24
	WALL WORKS		€ 61.786,11
	CEILING WORKS		€ 93.609,21
	WALL FINISHES WORKS		€ 79.163,15
	ALUMINIUM-GLASS WORKS & DOORS		€ 49.495,95
	JOINERY WORKS		€ 111.242,37
	OTHER DECORATION WORKS & EQUIPMENT		€ 68.072,80
	BRANDING		€ 26.715,54
Electrical	ELECTRIC PANELS	€ 168.770,65	€ 9.328,27
	HEAVY CURRENT FEEDING CABLES		€ 4.160,96
	CABLE TRAYS & PIPES		€ 12.169,20
	SWITCHES AND SOCKETS		€ 6.476,79
	SOCKET OUTLETS		€ 12.703,33
	LIGHTING FIXTURES		€ 6.190,43
	LIGHTING CABLES		€ 13.870,67
	FIRE DETECTION SYSTEM		€ 18.551,39
	DATA TELEPHONE SYSTEM		€ 29.291,17
	EMERGENCY ANNOUNCE SYSTEM		€ 6.888,58
	CCTV SYSTEM (IP CAMERAS) - Cabling Only		€ 891,94
	EARTHING INSTALLATIONS		€ 491,43
	UPS SYSTEM		€ 7.454,01
	LIGHTING AUTOMATION SYSTEM		€ 25.514,74
	AV SYSTEM		€ 5.143,11
	MECHANICAL AUTOMATION CABLING		€ 4.176,57
	CARD ACCESS and SECURITY SYSTEM - Piping Only		€ 967,36
	ENGINEERING AND MOBILISATION WORKS		€ 4.500,71
Mechanical	SANITARY INSTALLATION	€ 197.151,33	€ 4.497,69
	HEATING AND COOLING SYSTEM - FANCOIL SYSTEM		€ 91.633,00
	VENTILATION INSTALLATION		€ 44.181,13
	FIRE FIGHTING SYSTEM		€ 33.288,54
	MECHANICAL AUTOMATION		€ 23.550,97
Lighting		€ 81.728,08	
	LIGHTING WORKS		€ 81.728,08





PROJECT NAME	The LEGO Group Istanbul Office Project	DATE	21.09.2026
LOCATION	Trump Tower	REV NO	1
Sqm (net)	720		
FILE NAME	ARCHITECTURAL BOQ		

CODE	WORK DESCRIPTION	BRAND / MARKA	PLACE / MAHAL	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(EUR)
A	GENERAL WORKS							€ 85.594,92
A.01	General Construction Works			Including Coordination of 3rd Party Procurements: Furniture, IT, AV, Planting etc.	mak./lps.	1,00	€ 6.586,40	€ 6.586,40
A.02	Protection Works			The floor and the walls of the common areas will be covered with styrofoam and OSB. The closed area should be created which restricts site personnel to enter common areas - the circulation will be provided from service elevator to the office space. Also facade windows Koruflex covering.	mak./lps.	1,00	€ 5.108,80	€ 5.108,80
A.03	As-Built Drawings Preparation Fee			(2 hard copy, 3 CDs)	mak/lps.	1,00	€ 3.293,20	€ 3.293,20
A.04	Site Mobilization			Portable fire extinguishers as per the decoration guideline should be provided.	mak/lps.	1,00	€ 12.932,46	€ 12.932,46
A.05	Health and Safety Engineer and Equipment			Full time C class of occupational safety specialist should be on site during the construction and material deliveries.	mak/lps.	1,00	€ 17.431,58	€ 17.431,58
A.06	Electricity Usage on site				mak/lps.	1,00	€ 1.240,00	€ 1.240,00
A.07	Water Usage on site				mak/lps.	1,00	€ 620,00	€ 620,00
A.08	Stamp Duty for the Contract				mak/lps.	1,00	€ 10.548,45	€ 10.548,45
A.09	All Risk Insurance			All Risk Insurance & 3rd Party Indemnity Insurance	mak/lps.	1,00	€ 5.470,38	€ 5.470,38
A.10	Detailed Cleaning			Two times: Before temporary acceptance and before first day in the office	pcs	1,00	€ 2.634,56	€ 2.634,56
A.11	Demolishment Works			As per the dismantling plan and Site Surveys by the Bidders	set	1,00	€ 10.560,20	€ 10.560,20
A.12	Debris Removal			Debris removal after the demolition, during the construction and debris removal for furniture, AV, IT, security etc. Teams.	set	1,00	€ 1.522,81	€ 1.522,81
A.13	Security Cost Markup			Just add the markup amount for the security scope defined under Security tab. The works will be conducted by a global vendor of LEGO - Inspired. The scope will be under your contract	set	1,00	€ 4.133,33	€ 4.133,33
A.14	Site Filming and Editing Works			2 Cameras will be located at site for filming, superlapse film will be developed from those. Editing and preparing a video cost by agency should be considered here.	set	1,00	€ 2.415,01	€ 2.415,01
A.15	Cleaning of the Existing Office			Following the furniture removal from existing office, rough cleaning (kaba temizlik) and removal of the remaining materials.	set	1,00	€ 1.097,73	€ 1.097,73
B	FLOOR WORKS							€ 96.630,24
B.01	Encapsulated raised floor with Calcium Sulfate Core	UNIGEN (Onto ENCA panel), ASPEN, ANIL ZEMİN or equivalent	General	Encapsulated	m2	662,34	€ 61,50	€ 40.736,92
B.02	Antistatic Raised Floor	UNIGEN (Onto ENCA panel), ASPEN, ANIL ZEMİN or equivalent	Server Room	Encapsulated Instead of VF-02 VINYL FLOOR FINISH	m2	10,00	€ 78,86	€ 788,56
B.03	CP-01 CARPET TILE	InterfaceStep it up Sage 9406201	Refer to Floor Finishes Drawings		Set	11,81	€ 57,66	€ 680,96
B.04	CP-02 CARPET TILE	InterfaceStep it up Terracotta 9406209	Refer to Floor Finishes Drawings		Set	48,43	€ 57,66	€ 2.792,47
B.05	CP-03 CARPET TILE	InterfaceConnected EthosObserve 4314004	Refer to Floor Finishes Drawings		m2	376,29	€ 53,94	€ 20.297,08
B.06	CP-04 CARPET TILE	InterfaceConnected EthosCaptivate 4314020	Refer to Floor Finishes Drawings		m2	18,55	€ 53,94	€ 1.000,59
B.07	FT-01 FLOOR TILE	Domus Meridian DLHS 05 Spin Décor	Refer to Floor Finishes Drawings		m2	10,00	€ 223,71	€ 2.237,09
B.08	VF-01 VINYL FLOOR FINISH	Forbo flooring Colorex EC	Refer to Floor Finishes Drawings	VF-01 Vinyl floor finishForbo flooring Colorex EC -EC 250206 - moonstoneRefer	m2	15,00	€ 43,40	€ 651,00
B.09	VF-02 VINYL FLOOR FINISH	Interface Norament CastelloCortege 5353	Refer to Floor Finishes Drawings	Interface Norament CastelloCortege 5353	m2	157,94	€ 156,24	€ 24.676,55
B.10	Transition Profile	Schluter Schiene A 60 Mat Bkack	As per the floor finishes plan (threshold notes)	As per the floor finishes plan (threshold notes)	mt	22,00	€ 28,59	€ 628,95
B.11	Dustproof Epoxy Primer	Sika, Weber or equivalent	Server Room		m2	9,48	€ 9,32	€ 88,40
B.12	Water Proof Isolation	BASF / Masterseal M 860	For the kitchenette	Sample to be presented	m2	1,00	€ 219,55	€ 219,55
B.13	Steel Reinforcement Works		Please consider speed gates especially	where necessary	kg	120,00	€ 3,44	€ 412,35
B.14	Installation of a custom curved floor transition profile around the teapoint ceramic perimeter				mtul	13,00	€ 43,91	€ 570,82
B.15	Installing a cement board substrate under the ceramic floor tiles in the tea point area				m2	10,00	€ 84,90	€ 848,95
C	WALL WORKS			All walls should be slab to slab				€ 61.786,11
C.01	P1 Two layers of Gyproc WallBoard 12.5mm each side of Gypframe 48 S 70 'C' studs at 600mm centres. 50mm Isover Acoustic Partition Roll in the cavity. For heights up to 4000mm. As per BG A206142(EN) or equal	KNAUF,LAFARGE,AMF	General		m2	3,07	€ 84,09	€ 257,81
C.02	P3 Two layers of Gyproc WallBoard 12.5mm each side of Gypframe 48 S 70 'C' studs at 600mm centres. 50mm Isover Acoustic Partition Roll in the cavity. For heights up to 4000mm. As per BG A206142(EN) or equal	KNAUF,LAFARGE,AMF	General	For kitchenette, it should be WR	m2	339,60	€ 84,09	€ 28.555,83
C.03	P3B Two layers of Gyproc WallBoard 12.5mm each side of Gypframe 48 S 70 'C' studs at 600mm centres. 50mm Isover Acoustic Partition Roll in the cavity. For heights up to 4000mm. As per BG A206142(EN) or equal	KNAUF,LAFARGE,AMF	General		m2	33,61	€ 92,98	€ 3.124,84
C.04	P3 Two layers of Gyproc WallBoard 12.5mm each side of Gypframe 48 S 70 'C' studs at 600mm centres. 50mm Isover Acoustic Partition Roll in the cavity. For heights up to 4000mm. As per BG A206142(EN) or equal	KNAUF,LAFARGE,AMF	General		mt	70,00	€ 45,63	€ 3.193,95
C.05	P4 One layer of Gyproc WallBoard 12.5mm each side of Gypframe 48 S 50 'C' studs at 600mm centres. For heights up to 2500mm. As per BG A206001 (EN) or equal	KNAUF,LAFARGE,AMF	General		m2	2,56	€ 49,52	€ 126,53
C.06	P7L Two layers of Gyproc WallBoard 12.5mm to one side of Gypframe 48 S 50 'C' Studs at 600mm centres	KNAUF,LAFARGE,AMF	General		m2	194,84	€ 49,52	€ 9.649,04
C.07	Gypsum Board Above the Glass Partition	KNAUF,LAFARGE,AMF	All Office	P3L Bulkhead	mt		€ 76,81	€ 0,00
C.08	Gypsum Board Under the Glass Partition	KNAUF,LAFARGE,AMF	All Office		mt	30,52	€ 54,58	€ 1.665,65
C.09	Plywood on the Walls		All Office	"PLY" coding	m2	111,73	€ 74,38	€ 8.311,20
C.10	Sound Insulation Strip	KNAUF,LAFARGE,AMF	on all joint points		mt	420,00	€ 2,02	€ 848,95
C.11	Steel Reinforcement for the Heavy Equipments to be hanged where necessary				kg	1200,00	€ 3,44	€ 4.123,49
C.12	Gypsum board edge screw fixing				mtul	198,80	€ 9,70	€ 1.928,82
D	CEILING WORKS							€ 93.609,21
D.01	CT-01 ACOUSTIC FELT CEILING	Feltouch Custom FLT06		Refer to Reflected Ceiling Plan	m2	14,43	€ 380,56	€ 5.491,42
D.02	CT-02 ACOUSTIC FEATURE CEILING	Feltouch Custom FLT06		Refer to Reflected Ceiling Plan	m2	19,87	€ 460,03	€ 9.140,75
D.03	CT-03 VAULTED CEILING	Feltouch Volta La-InFLM-0		Refer to Reflected Ceiling Plan	mt	26,13	€ 226,82	€ 5.926,74
D.04	CTL-01 METAL MESH CEILING SYSTEM	Custom Made		systemTo be specified by GC, subject to design team approvalPowder coat in PC-02141 LEGO Earth GreenRefer to Reflected Ceiling	m2	25,81	€ 130,58	€ 3.370,32
D.05	CTP-01 MF PLASTERBOARD CEILING	KNAUF,LAFARGE,AMF		Steel box profiles	m2	303,50	€ 47,30	€ 14.355,19
D.06	CTX-02 EXPOSED CEILING WITH ACOUSTIC SPRAY PAINT - BLUE	Acosorb or similar Acospray DC2 1.0		CTX- 02 Exposed ceiling with Acoustic spray and paint To be spray painted LEGO light cornflower Refer to Reflected Ceiling Plan	m2	186,60	€ 94,24	€ 17.585,18
D.07	CTX-03 EXPOSED CEILING WITH ACOUSTIC SPRAY PAINT - GREEN	Acosorb or similar Acospray DC2 1.0		CTX- 02 Exposed ceiling with Acoustic spray and paint To be spray painted LEGO Minty Green Refer to Reflected Ceiling Plan	m2	94,59	€ 94,24	€ 8.914,16
D.08	CTX-04 EXPOSED ACOUSTIC SPRAY PAINT ABOVE CTL-01	Acosorb or similar Acospray DC2 1.0			m2	29,95	€ 96,72	€ 2.896,76
D.09	Access Hatches where necessary	Tempo	where necessary		pcs	15,00	€ 72,77	€ 1.091,51
D.10	Ceiling Bulkhead	KNAUF,LAFARGE,AMF			mt	187,28	€ 30,32	€ 5.678,28
D.11	Gypsumboard Ceiling Plastering	KNAUF,LAFARGE,AMF			m2	303,50	€ 9,16	€ 2.781,37
D.12	Gypsumboard Ceiling Painting	KNAUF,LAFARGE,AMF			m2	303,50	€ 9,29	€ 2.820,42
D.13	Ceiling Bulkhead Plastering	KNAUF,LAFARGE,AMF			mt	187,28	€ 5,31	€ 995,36



PROJECT NAME The LEGO Group Istanbul Office Project
LOCATION Trump Tower
Sqm (net) 720
FILE NAME ARCHITECTURAL BOQ

DATE 21.09.2026
REV NO 1

CODE	WORK DESCRIPTION	BRAND / MARKA	PLACE / MAHAL	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(EUR)
D.14	Ceiling Bulkhead Painting	KNAUF LAFARGE AMF			mt	187,28	€ 4,94	€ 925,70
D.15	Curtain bulkhead Type-A (2X)	KNAUF LAFARGE AMF			mtul	47,17	€ 56,60	€ 2.669,67
D.16	Curtain bulkhead Type-B (2X)	KNAUF LAFARGE AMF			mtul	60,77	€ 113,19	€ 6.878,78
D.17	Curtain bulkhead Type-C (2X)	KNAUF LAFARGE AMF			mtul	27,11	€ 56,60	€ 1.534,34
D.18	Curtain bulkhead Type-D (5X)	KNAUF LAFARGE AMF			mtul	3,91	€ 141,49	€ 553,23
E	WALL FINISHES WORKS			Refer to Wall Finishes Drawings & Finishes Schedule				€ 79.163,15
E.01	PT- 01 Paint finish	Fill Boya/MarshallJotun			m2	1161,16	€ 16,47	€ 19.119,63
E.01L	PT- 01 Paint finish	Fill Boya/MarshallJotun			mt	1013,54	€ 8,78	€ 8.900,78
E.12	WT-01 Wall Tile	Domus Meridian DLHS 05 Spin Décor		Refer to Joinery drawings	m2	5,00	€ 223,71	€ 1.118,55
E.13	AP - 01 Acoustic Panel	Feltouch Custom Piece FLM-31			m2	7,80	€ 332,32	€ 2.592,06
E.14	AP - 02 Acoustic Panel	Feltouch Custom Piece FLM-36			m2	6,29	€ 285,29	€ 1.793,90
E.15	AP - 03 Acoustic Panel	Feltouch Custom Piece FLM-07			m2	8,64	€ 305,72	€ 2.641,46
E.16	AP - 04 Acoustic Panel	Feltouch Custom Piece FLM-02			m2	5,28	€ 330,40	€ 1.744,51
E.17	AP - 05 Acoustic Panel	Feltouch Custom Piece FLM-24			m2	8,28	€ 319,02	€ 2.641,46
E.18	AP - 06 Acoustic Panel	Feltouch Custom Piece FLM-26			m2	5,28	€ 330,40	€ 1.744,51
E.19	AP - 07 Acoustic Panel	Feltouch Custom Piece FLM-45			m2	20,05	€ 199,18	€ 3.993,22
E.20	AP - 08 Acoustic Panel	Feltouch Custom Piece FLM-06			m2	3,49	€ 216,10	€ 754,63
E.21	AP - 09 Acoustic Panel	Feltouch Custom Piece FLT-02			m2	10,20	€ 144,11	€ 1.469,90
E.22	AP - 10 Acoustic Panel	Feltouch Custom Piece FLM-41			m2	8,18	€ 269,94	€ 2.208,11
E.23	AP - 11 Acoustic Panel	Feltouch Custom Piece FLM-25			m2	8,18	€ 269,94	€ 2.208,11
E.24	CT - 01 Curtain	Kvadrat Linex II 0130			m2	96,00	€ 134,92	€ 12.952,74
E.25	CT - 02 Curtain	Kvadrat Daybreak 2 0521			m2	18,00	€ 169,67	€ 3.054,05
E.26	CT - 03 Curtain	Kvadrat Melu Acoustic 0138			m2	20,00	€ 362,08	€ 7.241,60
E.27	Gypsumboard Wall Plastering			Behind furniture, plaster without paint	m2	102,83	€ 8,87	€ 911,86
E.28	Gypsumboard Wall Plastering				mtul	377,52	€ 5,49	€ 2.072,08
F	ALUMINIUM-GLASS WORKS & DOORS			Please share the specs of the proposed model with specs and test reports within submission pack.				€ 49.495,95
F.01	P22 Double Glazed Partition	Trimline, Aspen		NFR. Deflection Head Track as per building requirements. P3 bulkhead above the glazing. 50mm Acoustic Baffle below RAF. Track colour ref. to Finishes Schedule.	m2	31,15	€ 400,97	€ 12.490,10
F.02	Technical Panel	Trimline, Aspen		To accomate room schedules and sockets, switches	pcs	8,00	€ 373,67	€ 2.989,33
F.03	JB Double Glazed, Double Leaf Door	Trimline, Aspen		Swing/Hinged, NFR, Aluminum Frame, Rw min.42dB 1700x2500	pcs	1,00	€ 2.941,04	€ 2.941,04
F.04	GA Double Glazed, Single Leaf Door	Trimline, Aspen		Swing/Hinged, NFR, Aluminum Frame, Rw min.42dB 1030 x 2500	pcs	9,00	€ 1.841,12	€ 16.570,06
F.05	BB Solid, 1.5 Leaf Door			Swing/Hinged, Fire Rating FD 30s, Timber Frame, No VP, Rw min. TBC 1600 x 2500	pcs	1,00	€ 4.866,65	€ 4.866,65
F.06	AB Solid, Single Leaf Door			Swing/Hinged, NFR, Timber Frame, Vision Panel, Rw min. TBC 1030 x 2500	pcs	2,00	€ 1.412,47	€ 2.824,94
F.07	AA Solid, Single Leaf Door			Swing/Hinged, Fire Rating, Timber Frame, Vision Panel, Rw min. TBC 1030 x 2500	pcs	1,00	€ 1.412,47	€ 1.412,47
F.08	Skirting	8 cm MDF		Same color with the walls		250,00	€ 16,47	€ 4.116,50
F.09	Supply and installation of custom bent aluminum profiles for arched doors				mtul	42,00	€ 30,59	€ 1.284,86
G	JOINERY WORKS							€ 111.242,37
G.01	J01 RECEPTION DESK				set	1,00	€ 10.424,06	€ 10.424,06
G.02	J02 RECEPTION STORAGE				set	1,00	€ 8.342,78	€ 8.342,78
G.03	J03 RECEPTION PLANTER				set	1,00	€ 8.589,85	€ 8.589,85
G.04	J04 GAMES RM SHELIVING				set	1,00	€ 12.231,61	€ 12.231,61
G.05	J05 MULTIPURPOSE RM JOINERY				set	1,00	€ 3.700,41	€ 3.700,41
G.06	J06 1P BOOTH SEATING				set	1,00	€ 3.039,81	€ 3.039,81
G.07	J07 PRINT ROOM UNITS				set	1,00	€ 3.078,70	€ 3.078,70
G.08	J08 PRINT ROOM SHELIVING				set	1,00	€ 1.082,40	€ 1.082,40
G.09	J10 TEAPOINT UNITS				set	1,00	€ 10.386,86	€ 10.386,86
G.10	J11 TEAPOINT ISLAND				set	1,00	€ 7.617,69	€ 7.617,69
G.11	J12 TEAPOINT TIERED SEATING				set	1,00	€ 15.843,50	€ 15.843,50
G.12	J13 FEATURE STORAGE				set	1,00	€ 19.024,58	€ 19.024,58
G.13	J14 COLLABORATION WALL SHELVES				set	1,00	€ 533,20	€ 533,20
G.14	J16 BOARDROOM DISPLAY SHELIVING				set	1,00	€ 1.727,57	€ 1.727,57
G.15	J17 STOOL STORAGE				set	1,00	€ 2.559,36	€ 2.559,36
H	OTHER DECORATION WORKS & EQUIPMENT			Please specify the model you proposed in the F column, if it is different than the original				€ 68.072,80
H.01	EQ-01 – Built-in fridge/freezer	Bosch – Series 4 – KIN86VSE0G		https://www.bosch-home.co.uk/en/product/fridges-freezers/fridge-freezers/built-in-fridge-freezers/freezer-at-bottom-KIN86VSE0G	pcs	2,00	€ 2.180,76	€ 4.361,52
H.02	EQ-02 – Coffee Machine	WMF 5000 S+		WMF 5000 S+		1,00	€ 17.161,60	€ 17.161,60
H.03	EQ-03 – Water tap	Borg and Overstrom – T3 – 1 – Steel or similar		https://borgandoverstrom.com/products/43#tab=specifications	pcs	1,00	€ 8.013,46	€ 8.013,46
H.04	EQ-04 – Single lever kitchen mixer	Pro Hansgrohe – Hansgrohe Talis M54 or similar approved – 72842000 – Chrome		https://pro.hansgrohe.co.uk/article/detail-talis-m54-single-lever-kitchen-mixer-210-ecosmart-with-pull-out-spray-2-spray-modes-72842000	pcs	1,00	€ 381,68	€ 381,68
H.05	EQ-05 – Sink	Reginox or similar approved – Reginox - Ohio 40 x 40 – OHIO 40X40 L – Stainless Steel (304)		https://www.reginox.co.uk/product/range/ohio-40x40	pcs	1,00	€ 101,43	€ 101,43
H.06	EQ-06 – Integrated Microwave	Bosch – Series 4 – BFL523MB0B – Black		https://www.bosch-home.co.uk/en/product/cooking-baking/microwaves/built-in-microwaves/BFL523MB0B	pcs	1,00	€ 551,06	€ 551,06
H.07	EQ-07 – Fully integrated Dishwasher	Bosch – Series 6 – SMV6ZCX10G – 515x598x550 mm		https://www.bosch-home.co.uk/en/product/dishwashers/built-in-dishwashers/built-in-dishwashers/60width/SMV6ZCX10G	pcs	1,00	€ 810,17	€ 810,17
H.08	EQ-08 – Pull Out Waste Bin	Vauth-Sagel – Pull Out Waste Bin, 600 mm, Vauth-Sagel VS ENVI Space XX Pro S/Pro – 503.VS44.313 – Lava Grey – For cabinet width 600 mm, depth 515 mm, 2x 44 litres		https://www.hafele.co.uk/en/product/pull-out-waste-bin-600-mm-vauth-sagel-vs-envi-space-xx-pro-s-pro/	pcs	3,00	€ 627,08	€ 1.881,24
H.09	EQ-09 – Built-under fridge	Bosch – Series 4 – KUR21VFE0G		https://www.bosch-home.co.uk/en/product/fridges-freezers/fridges/built-in-fridges-without-freezer-section/KUR21VFE0G	pcs	1,00	€ 1.570,83	€ 1.570,83



PROJECT NAME The LEGO Group Istanbul Office Project
LOCATION Trump Tower
Sqm (net) 720
FILE NAME ARCHITECTURAL BOQ

DATE 21.09.2026
REV NO 1

CODE	WORK DESCRIPTION	BRAND / MARKA	PLACE / MAHAL	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(EUR)
H.10	EQ-10 – Integrated Paper Towel Dispenser	Bobrick or similar approved – Countertop-Mounted Paper Towel Dispenser, 300 Multifold Towels – B-526 – Satin finish – Cutout: 12 1/4" W (310mm), 4 1/2" front to back depth (115mm), 3/4" to 1 1/2" (19 to 38mm)		https://www.bobrick.com/product/b-526/	pcs	1,00	€ 694,40	€ 694,40
H.11	EQ-12 – Storage racking			GC to advise on available items in Istanbul market. – TBC – 2200mm / 1200mm / 400-500mm max	pcs	6,00	€ 261,42	€ 1.568,51
H.12	Manuel Sunscreen	Permisan	All Office		m2	272,00	€ 24,18	€ 6.576,96
H.13	Manuel Black-out	Permisan	All Office		m2	272,00	€ 25,42	€ 6.914,24
H.14	Motorized Sunscreen	Permisan	Meeting Rooms		m2	110,00	€ 47,12	€ 5.183,20
H.15	Motorized Black-out	Permisan	Meeting Rooms		m2	110,00	€ 48,36	€ 5.319,60
H.16	Came 900mm Speedstile lane	Came Ozak	Reception	Please check the security tab	set	1,00	€ 6.809,46	€ 6.809,46
H.17	Safe Box	As per the specs shared		Amazon Basics Steel Home Security Safe Box with Electronic Keypad Lock for Documents, Jewelry, Valuables, 1.8 Cubic Feet, Black, 13.8"W x 13"D x 19.7"H	pcs	1,00	€ 173,44	€ 173,44
I	BRANDING			Please refer to "LEGO Istanbul_BX GC Pack_110826" document for the details.				€ 26.715,54
I.1	Models & Installations							
I.1.1	1 Interactive light artwork	Coordination & LED connection & Cabling		This artwork is an interactive LED wall, faceted by lego panels. The LEDs will respond to movement and create a rippling effect behind the transparent LEGO brick panels. It is set into a niche and the panels are attached from the front. While this is still in development, we would be sharing all technical drawings including wiring and installation instructions as well as a clear purchase order for all necessary components. The lego face panels will come pre-built and ready for installation, but we would like ideally for you to oversee an electrician who is capable of installing the LED wall behind. We will have someone on site to advise and test.	set	1,00	€ 362,95	€ 362,95
I.1.2	2 Abstract LEGO artwork	Provided by LEGO Group Move from Delivery Point of the Building Installation and Mount		This is an abstract LEGO artwork that will be premade and ready for installation. Delivered to site by the Lego Group - gc to install/mount	set	1,00	€ 219,55	€ 219,55
I.1.3	3 LEGO hanging evil eyes	Provided by LEGO Group Move from Delivery Point of the Building Installation and Mount		This installation will consist of a number of premade hanging evil eyes. The artwork will be premade and ready for hanging. Layout will be shared.	set	1,00	€ 329,32	€ 329,32
I.1.4	1 Team Photo Wall	GC to purchase frames, print, frame and install according to detail design		This is a wall of framed photos installed over a graphic decal. Photo frames will be specified for order and photos will be printed ready for collection locally and framing. A clear elevation will be provided for hanging instructions.	set	1,00	€ 1.436,93	€ 1.436,93
I.1.5	2 LEGO plate wall	Provided by LEGO Group Move from Delivery Point of the Building Installation and Mount		LEGO base plates installed to the wall with container system for bricks. Drawings to be provided by M Moser.	set	1,00	€ 219,55	€ 219,55
I.1.6	3 Community minifigure wall	Community Wall: Staff minifigure. GC to fabricate and install according to detail design. Minifigure components provided by LEGO Group		LEGO base plates and surrounding framing and tile installed to the wall. Instructions and elevation provided.	set	1,00	€ 329,32	€ 329,32
I.1.7	4 LEGO Backgammon	LEGO Backgammon. GC to fabricate and install board according to detail design. Backgammon pieces to be provided by LEGO and delivered to site.		Magnetic backgammon board installed to the wall (design detail drawings and specifications provided). Magnetic LEGO backgammon pieces provided.	set	1,00	€ 219,55	€ 219,55
I.1.8	1 LEGO History Wall	History Wall. GC to fabricate and install according to detail design		LEGO History wall to be fabricated and installed. Design and production artwork shared by M Moser. (LEGO History wall production guide can be found in this folder)	set	1,00	€ 1.613,67	€ 1.613,67
I.2	Wall+Glazing Graphics							
I.2.1	Graphic Stories Walls			GRAPHIC STORIES (WALL) Material: Diecut matte vinyl sticker (NON-PVC) Installation: Mount onto wall surface Colour: To match LEGO Blue Velvet	m2	69,35	€ 148,80	€ 10.319,28
I.2.2	Graphic Stories Glazing			GRAPHIC STORIES (GLAZING) Material: Super clear transparent vinyl film fill coverage (NON-PVC). Distraction privacy band in dusted crystal finish Colour: Graphic to be UV printed double-sided with white underpin (based on zone colours) Installation: Mount onto front glazing	m2	57,30	€ 136,40	€ 7.815,72
I.3	Signage & Wayfinding			Please refer to key plan for that. Page 27 of "LEGO Istanbul_BX GC Pack_110826" document for the details and materials.				
I.3.1	Room ID				pcs	6,00	€ 58,65	€ 351,91
I.3.2	Projected ID				pcs	9,00	€ 117,30	€ 1.055,74
I.3.3	Facility ID				pcs	3,00	€ 58,65	€ 175,96
I.3.4	BOH Room ID				pcs	1,00	€ 58,65	€ 58,65
I.3.5	Bins				pcs	3,00	€ 138,63	€ 415,90
I.3.6	Directional				pcs	2,00	€ 362,58	€ 725,15
I.4	Manhour Works for Logo and LEGO cats				set	1,00	€ 1.066,40	€ 1.066,40
ARCHITECTURAL WORKS TOTAL								€ 672.310,29
ARCHITECTURAL OPTIONAL WORKS								€ 153,68
AO.01	Manhour Cost for Move Personnel				manhour	1,00	€ 76,84	€ 76,84
AO.02	Manhour Cost for Move Personnel				manhour	1,00	€ 76,84	€ 76,84

Note: All architectural finishes, branding items, local lighting fixtures will be presented for material approval. Please consider material preparation for those items in your scope.
For any request of material and shop-drawing approval, the forms have to be sent out at least 48 hours prior to the expected approval date

CODE	WORK DESCRIPTION	BRAND / MARKA	PLACE / MAHAL	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(EUR)
A	ELECTRIC PANELS							€ 9.328,27
A.01	SDB- Main Distribution Panel	PANEL SHEET: EAE,SIEMENS, SCHNEIDER SWITCHING EQUIPMENT: SIEMENS, ABB, SCHNEIDER		The panel should have a Type Test (ISO and TSE documents should also be included) report.	pcs	1,00	€ 5.614,00	\$5.614,00
A.02	LMB - Main Distribution Panel	PANEL SHEET: EAE,SIEMENS, SCHNEIDER SWITCHING EQUIPMENT: SIEMENS, ABB, SCHNEIDER		The panel should have a Type Test (ISO and TSE documents should also be included) report.	pcs	1,00	€ 3.714,27	\$3.714,27
B	HEAVY CURRENT FEEDING CABLES							€ 4.160,96
B.01	3x2,5 mm² NHXMH	PRYSMIAN-NEXANS			m	400,00	€ 3,37	€ 1.346,26
B.02	4x2,5 mm² NHXMH	PRYSMIAN-NEXANS			m	120,00	€ 4,42	€ 529,89
B.03	3x2,5 mm² N2XH FE180	PRYSMIAN-NEXANS			m	80,00	€ 4,20	€ 336,36
B.04	5x10 N2XH	PRYSMIAN-NEXANS			m	40,00	€ 21,37	€ 854,63
B.05	3x25+16 N2XH	PRYSMIAN-NEXANS			m	25,00	€ 37,50	€ 937,52
B.06	1X16 H7Z1-K	PRYSMIAN-NEXANS			m	25,00	€ 6,25	€ 156,28
C	CABLE TRAYS & PIPES							€ 12.169,20
C.01	Cable Trays 100 mm (Pregalvaniz)	EAE			m	112,00	€ 12,43	€ 1.391,87
C.02	Cable Trays 200 mm (Pregalvaniz)	EAE			m	150,00	€ 19,92	€ 2.987,30
C.03	Cable Trays 300 mm (Pregalvaniz)	EAE			m	231,00	€ 26,74	€ 6.177,53
C.04	Cable Stairs 200 mm (Pregalvaniz)	EAE			m	9,00	€ 16,52	€ 148,66
C.05	Cable Stairs 300 mm (Pregalvaniz)	EAE			m	9,00	€ 19,38	€ 174,42
C.06	3/4" EMT Pipe (Accessories Included) (Painted)	AFI, ALEX			m	33,00	€ 7,27	€ 239,83
C.07	1/2" EMT Pipe (Accessories Included) (Painted)	AFI, ALEX			m	55,00	€ 9,16	€ 503,55
C.08	Q20 Halogen Free Spiral Pipe (Accessories Included)	IPEK, CANLAR, ENSMET			m	950,00	€ 0,57	€ 546,03
D	SWITCHES AND SOCKETS							€ 6.476,79
D.01	Light Button-1M (Mechanism cover included)	BTICINO LIVING NOW (Cream Socket)			pcs	23,00	€ 13,10	€ 301,21
D.02	2M Base + Cabinet	BTICINO LIVING NOW (Cream Socket)			pcs	7,00	€ 11,67	€ 81,71
D.03	4M Base + Cabinet	BTICINO LIVING NOW (Cream Socket)			pcs	3,00	€ 17,56	€ 52,68
D.04	Power Socket (Service/Wall Mounted)-The mechanism cover, base, and housing are included.	BTICINO LIVING NOW (Cream Socket)			pcs	29,00	€ 22,30	€ 646,74
D.05	Double Power Socket (Service/Wall Mounted)-The mechanism cover, base, and housing are included.	BTICINO LIVING NOW (Cream Socket)			pcs	6,00	€ 39,32	€ 235,94
D.06	Four Gang Power Socket (Service/Wall Mounted)-The mechanism cover, base, and housing are included.	BTICINO LIVING NOW (Cream Socket)			pcs	1,00	€ 78,65	€ 78,65
D.07	Wall Socket Block (2 Schuko - 2 Data)-The mechanism cover, base, and housing are included.	BTICINO LIVING NOW (Cream Socket)			pcs	7,00	€ 85,40	€ 597,78
D.08	Double Power Socket Cover (Service/Wall Mounted)-The mechanism cover, base, and housing are included.	BTICINO LIVING NOW (Cream Socket)			pcs	2,00	€ 39,32	€ 78,65
D.09	Floor Socket IP44	LEGRAND			pcs	4,00	€ 113,01	€ 452,04
D.10	T1 (2"Socket) Type table top burotilcal block)	BUROTIC BLOCK: XOM SOCKET: LEGRAND			pcs	2,00	€ 31,20	€ 62,40
D.11	T2 (4"Socket) Type table top burotilcal block)	BUROTIC BLOCK: XOM SOCKET: LEGRAND			pcs	57,00	€ 44,65	€ 2.545,32
D.12	T3 (8"Socket) Type table top burotilcal block)	BUROTIC BLOCK: XOM SOCKET: LEGRAND			pcs	1,00	€ 82,43	€ 82,43
D.13	Raised Floor Grommets	LEGRAND-EAE			pcs	41,00	€ 30,76	€ 1.261,26
E	SOCKET OUTLETS							€ 12.703,33
E.01	Main Supply Outlet (3x2,5 NHXNH Cable)	PRYSMIAN-NEXANS			pcs	33,00	€ 93,35	€ 3.080,44
E.02	T1 Burotic Outlet (3x2,5 NHXNH Cable)	PRYSMIAN-NEXANS			pcs	5,00	€ 77,28	€ 386,42
E.03	T2 Burotic Outlet (3x2,5 NHXNH Cable)	PRYSMIAN-NEXANS			pcs	57,00	€ 77,28	€ 4.405,17
E.04	T3 Burotic Outlet (3x2,5 NHXNH Cable)	PRYSMIAN-NEXANS			pcs	1,00	€ 77,28	€ 77,28
E.05	Motorized Curtain Outlet (4x2,5 NHXNH Cable)	PRYSMIAN-NEXANS			pcs	17,00	€ 120,41	€ 2.046,96
E.06	Mechanical Outlet (3x2,5 NHXNH Cable)	PRYSMIAN-NEXANS			pcs	29,00	€ 93,35	€ 2.707,05
F	LIGHTING FIXTURES							€ 6.190,43
F.01	LT-01 Linear light inbetween acoustic ceiling panels-Dali	INSTALLATION ONLY			pcs	8,00	€ 27,44	€ 219,55
F.02	LT-02 Diameter1350mm Recessed pendant light-Dali	INSTALLATION ONLY			pcs	2,00	€ 27,44	€ 54,89
F.03	LT-03 Diameter 600mm Recessed pendant light-Dali	INSTALLATION ONLY			pcs	2,00	€ 27,44	€ 54,89
F.04	LT-04 900x1400mm Suspended acoustic raft with integrated linear light-Dali	INSTALLATION ONLY			pcs	2,00	€ 27,44	€ 54,89
F.05	LT-05A 1200x2400 mm Suspended acoustic raft with integrated linear lights-Dali	INSTALLATION ONLY			pcs	6,00	€ 27,44	€ 164,66
F.06	LT-05B 1200x2400mm Suspended acoustic raft with integrated linear lights-Dali	INSTALLATION ONLY			pcs	5,00	€ 27,44	€ 137,22
F.07	LT-06A 1200x600mm Suspended acoustic raft with integrated linear light-Dali	INSTALLATION ONLY			pcs	1,00	€ 27,44	€ 27,44
F.08	LT-06B 1200x600mm Suspended acoustic raft with integrated linear light-Dali	INSTALLATION ONLY			pcs	1,00	€ 27,44	€ 27,44
F.09	LT-07 240x600 Suspended acoustic raft with integrated linear light-Dali	INSTALLATION ONLY			pcs	1,00	€ 27,44	€ 27,44
F.10	LT-08 Suspended Pendant light-Dali	INSTALLATION ONLY			m	1,00	€ 27,44	€ 27,44
F.11	LT-09 Wall Light-Dali	INSTALLATION ONLY			pcs	2,00	€ 27,44	€ 54,89
F.12	LT-10 200x1256mm Suspended Pendant light-Dali	INSTALLATION ONLY			pcs	1,00	€ 27,44	€ 27,44
F.13	LT-11 1900mm Suspended Pendant light-Dali	INSTALLATION ONLY			pcs	1,00	€ 27,44	€ 27,44
F.14	LT-12 Suspended Pendant light-Dali	INSTALLATION ONLY			pcs	2,00	€ 27,44	€ 54,89
F.15	LT-13 Recessed downlight-Dali	INSTALLATION ONLY			pcs	34,00	€ 27,44	€ 933,07
F.16	LT-14 240x800mm Suspended acoustic raft with integrated linear light	INSTALLATION ONLY			pcs	1,00	€ 27,44	€ 27,44
F.17	LT-15 Wall Light-Dali	INSTALLATION ONLY			pcs	2,00	€ 27,44	€ 54,89
F.18	LT-16 Suspended Can Lights-Dali	INSTALLATION ONLY			pcs	52,00	€ 27,44	€ 1.427,05
F.19	LT-17 EXISTING LEGO Pendant light	INSTALLATION ONLY			pcs	1,00	€ 27,44	€ 27,44
F.20	LT-18 Linear profile light	INSTALLATION ONLY			pcs	1,00	€ 27,44	€ 27,44
F.21	LT-19 Concealed LED Strip	INSTALLATION ONLY			m	60,00	€ 13,63	€ 829,89
F.22	Emergency Battery Kit	Installation & Supply			pcs	30,00	€ 47,96	€ 1.438,67
F.23	Exit	Installation & Supply			pcs	9,00	€ 51,56	€ 464,02
G	LIGHTING CABLES							€ 13.870,67
G.01	Switchless Lighting Outlet (3x2,5 NHXNH Cable)	PRYSMIAN-NEXANS			pcs	20,00	€ 102,24	€ 2.044,74
G.02	Parallel Lighting Outlet (3x2,5 NHXNH Cable)	PRYSMIAN-NEXANS			pcs	106,00	€ 84,64	€ 8.972,27
G.03	Exit Lighting Outlet (3x2,5 N2XH FE180 Cable)	PRYSMIAN-NEXANS			pcs	9,00	€ 73,17	€ 658,54
G.04	Battery Kit Outlet (3x2,5 N2XH FE180 Cable)	PRYSMIAN-NEXANS			pcs	30,00	€ 73,17	€ 2.195,13
H	FIRE DETECTION SYSTEM							€ 16.551,39
H.01	Interactive Digital Addressable Smoke Detector	SIEMENS			pcs	44,00	€ 174,37	€ 7.672,48
H.02	Interactive Digital Addressable Combined Detector	SIEMENS			pcs	2,00	€ 214,36	€ 428,72
H.03	Interactive Digital Addressable Detector Socket	SIEMENS			pcs	46,00	€ 23,70	€ 1.090,27
H.04	Interactive Digital Addressable Alarm Button	SIEMENS			pcs	2,00	€ 199,85	€ 399,71
H.05	Elektronical Addressable Horn With Flashor	SIEMENS			pcs	2,00	€ 217,40	€ 434,80
H.06	Interactive Digital Addressable Role Module	SIEMENS			pcs	1,00	€ 557,60	€ 557,60
H.07	Siren Module	SIEMENS			pcs	1,00	€ 740,72	€ 740,72
H.08	Power Supply Module	SIEMENS			pcs	1,00	€ 468,26	€ 468,26
H.09	LED Indicator	SIEMENS			pcs	19,00	€ 29,89	€ 567,87
H.10	2x2x1 3/4" 8 mm² JH(gt)H FE 180/ E90	ERSE-2M			m	650,00	€ 4,83	€ 3.138,50
H.11	2x1,5 LIHCH FE 180/ E90	ERSE-2M			m	80,00	€ 2,98	€ 238,45
H.12	Testing & Commissioning	SIEMENS			set	1,00	€ 1.844,94	€ 1.844,94
I	DATA TELEPHONE SYSTEM							€ 29.291,17
	COPPER HORIZONTAL CABLING SYSTEM CAT6A FTP							
I.01	Patch Panel 24 Port (CAT6A) - Empty	COMSCOPE			pcs	4,00	€ 74,15	€ 296,61
I.02	RJ45 Cat6A S/FTP keystone jack (Patch Panel Side)	COMSCOPE			pcs	96,00	€ 15,89	€ 1.525,41
I.03	RJ45 Cat6A S/FTP, 1 module, keystone jack+faceplate	COMSCOPE			pcs	74,00	€ 17,58	€ 1.301,26
I.04	Surface mount box, 1 or 2 ports, for keystone connectors	COMSCOPE			pcs	16,00	€ 7,42	€ 118,72
I.05	CAT6A S/FTP Cable	COMSCOPE			m	2975,00	€ 2,54	€ 7.563,50
I.06	S/FTP patch cord, Cat6A, LSZH, 0,3 m, grey (WiFi)	COMSCOPE			pcs	16,00	€ 13,98	€ 223,69
I.07	S/FTP patch cord, Cat6A, LSZH, 0,3 m, grey (P.Panel)	COMSCOPE			pcs	74,00	€ 13,98	€ 1.034,74
I.08	S/FTP patch cord, Cat6A, LSZH, 1 m, grey (Table Point)	COMSCOPE			pcs	61,00	€ 13,98	€ 852,96
I.09	S/FTP CAT6A Termination	CONTRACTOR			pcs	74,00	€ 21,19	€ 1.567,78
I.10	S/FTP CAT6A Testing, Reporting, Labeling	CONTRACTOR			pcs	74,00	€ 12,71	€ 940,67
J	IT ROOM							€ 6.888,58
J.01	Speaker (Flush mounted)	BOSCH			pcs	29,00	€ 152,72	€ 4.428,78
J.02	Speaker (Surface Mounted)	BOSCH			pcs	1,00	€ 169,93	€ 169,93
J.03	2x1,5 mm² LIHCH FE180 Cable	ERSE-2M			m	495,00	€ 2,98	€ 1.475,38
J.04	Testing & Commissioning				pcs	1,00	€ 814,49	€ 814,49



PROJECT NAME The LEGO Group Istanbul Office Project
LOCATION Trump Tower
Sq.m (net) 720
FILE NAME ELECTRICAL BOQ

DATE 21.09.2026
REV NO 1

CODE	WORK DESCRIPTION	BRAND / MARKA	PLACE / MAHAL	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(EUR)
K	CCTV SYSTEM (IP CAMERAS) - Cabling Only							€ 891,94
K.01	CAT6A S/FTP Cable	COMSCOPE			m.	225,00	€ 2,54	€ 572,03
K.02	S/FTP patch cord, Cat6A, LSZH, 0.3 m, grey (CCTV)	COMSCOPE			pcs	5,00	€ 12,50	€ 62,50
K.03	RJ45 Cat6A S/FTP, 1 module, keystone jack+faceplate	COMSCOPE			pcs	5,00	€ 17,58	€ 87,92
K.04	S/FTP CAT6A Termination	CONTRACTOR			pcs	5,00	€ 21,19	€ 105,93
K.05	S/FTP CAT6A Testing, Reporting, Labeling	CONTRACTOR			pcs	5,00	€ 12,71	€ 63,56
L	EARTHING INSTALLATIONS			The grounding/earthing of the electrical room and the newly installed cable trays shall be carried out.				€ 491,43
L.01	Server Room Earthing Bar Installation	AMPER-GERSAN-RADSAN	Server Room		pcs	3,00	€ 71,50	€ 214,51
L.02	1x6 mm² H07Z1-K cable	PRYSMIAN-NEXANS			m	50,00	€ 2,31	€ 115,28
L.03	6 mm² H07Z1-R Jumper	PRYSMIAN,NEXANS			pcs	200,00	€ 0,81	€ 161,63
M	UPS SYSTEM							€ 7.454,01
M.01	3 kVA, 1 Phase Input, 1 Phase Output, Rack Mount, Online RACK UPS With 30 min. Feed Time, SNMP	APC SRT5KRMXLI + SRT001/ APC SRT192RMBP ONLY INSTALLATION			pcs	1,00	€ 7.356,19	€ 7.356,19
M.02	Command socket 32A (IEC 60309 32 A)	Schneider			pcs	1,00	€ 97,82	€ 97,82
N	LIGHTING AUTOMATION SYSTEM			Lighting Automation System should consist of integrated presence&daylight sensors; this will be used in the open office, corridors, reception, kitchenette, breakout area, meeting rooms. Support functions will not have sensors. The computer for KNX Automation must be supplied by the employer.				€ 25.514,74
N.01	KNX Power Supply - 640 mA	ABB			pcs	2,00	€ 332,23	€ 664,45
N.02	Line Coupler	ABB			pcs	1,00	€ 363,97	€ 363,97
N.03	IP Router	ABB			pcs	1,00	€ 514,01	€ 514,01
N.04	KNX DALI Gateway - 2x64 DALI	ABB			pcs	3,00	€ 584,54	€ 1.753,63
N.05	24-Channel Switching Actuator	ABB			pcs	2,00	€ 785,49	€ 1.570,97
N.06	220/24 Power Supply	Meanwell			pcs	3,00	€ 39,86	€ 119,58
N.07	Interface	ABB			pcs	12,00	€ 100,31	€ 1.203,70
N.08	Presence Sensor	ABB			pcs	17,00	€ 241,41	€ 4.104,04
N.09	Presence and Daylight Sensor	ABB			pcs	30,00	€ 281,35	€ 8.440,36
N.10	10" Touch Panel	Astrum			pcs	2,00	€ 919,14	€ 1.838,27
N.11	4" Touch Panel	Astrum			pcs	1,00	€ 546,32	€ 546,32
N.12	Testing And Commissioning	CONTRACTOR			pcs	1,00	€ 1.406,84	€ 1.406,84
N.13	2x2x08,+0,8 mm² EIB Bus Cable	ERSE-2M			m	600,00	€ 1,91	€ 1.148,14
N.14	2x1 LIHCH Dali Line Cable	ERSE-2M			m	880,00	€ 2,09	€ 1.840,43
O	AV SYSTEM							€ 5.143,11
O.01	Patch Panel 24 Port (CAT6A) - Empty	COMSCOPE			pcs	1,00	€ 74,15	€ 74,15
O.02	RJ45 Cat6A S/FTP keystone jack (Patch Panel Side)	COMSCOPE			pcs	24,00	€ 15,89	€ 381,35
O.03	RJ45 Cat6A S/FTP, 1 module, keystone jack+faceplate	COMSCOPE			pcs	23,00	€ 17,58	€ 404,45
O.04	CAT6A S/FTP Cable	COMSCOPE			m.	925,00	€ 2,54	€ 2.351,67
O.05	S/FTP patch cord, Cat6A, LSZH, 0.5 m, grey (P.Panel)	COMSCOPE			pcs	23,00	€ 14,41	€ 331,35
O.06	S/FTP patch cord, Cat6A, LSZH, 1 m, grey (Table Point)	COMSCOPE			pcs	23,00	€ 16,10	€ 370,34
O.07	50mm AV Conduit in Floor	IPEK, CANLAR, ENSMET			m.	100,00	€ 2,66	€ 265,56
O.08	S/FTP CAT6A Termination	CONTRACTOR			pcs	23,00	€ 21,19	€ 487,28
O.09	S/FTP CAT6A Testing, Reporting, Labeling	CONTRACTOR			pcs	23,00	€ 12,71	€ 292,37
O.10	Floor Box	LEGRAND-EAE			pcs	6,00	€ 30,76	€ 184,57
P	MECHANICAL AUTOMATION CABLING							€ 4.176,57
P.01	Thermostat Mounting	CONTRACTOR		Field-side automation endpoints are included.	pcs	29,00	€ 15,37	€ 445,68
P.02	Mechanical Device Termination	CONTRACTOR		Field-side automation endpoints are included.	pcs	29,00	€ 35,13	€ 1.018,70
P.03	8x1 LIHCH Cable	ERSE-2M		Cable infrastructure for the thermostat	m.	280,00	€ 6,36	€ 1.781,18
P.04	3x1 LIHCH Cable	ERSE-2M		Cable infrastructure for the mechanical automation	m.	180,00	€ 2,83	€ 509,83
P.05	25mm Conduit	IPEK, CANLAR, ENSMET			m.	400,00	€ 1,05	€ 421,18
R	CARD ACCESS and SECURITY SYSTEM - Piping Only							€ 967,36
R0.1	100x100x75 Junction Box	CONTRACTOR			pcs	4,00	€ 14,73	€ 58,93
R0.2	25mm Conduit	IPEK, CANLAR, ENSMET		Cable details are specified in the security plan.	m.	60,00	€ 1,05	€ 63,18
R0.3	Coordination Fee			Cable details are specified in the security plan.	Set	1,00	€ 845,25	€ 845,25
S	ENGINEERING AND MOBILISATION WORKS							€ 4.500,71
S.01	Testing and Commissioning, Labeling, Mobilization	CONTRACTOR			pcs	1,00	€ 878,19	€ 878,19
S.02	Earthing Installation Test Report	CONTRACTOR			pcs	1,00	€ 768,41	€ 768,41
S.03	As-Built Projects	CONTRACTOR			pcs	1,00	€ 878,19	€ 878,19
S.04	Distribution Panel and Rack Cabinet Seismic Precautions	CONTRACTOR			pcs	1,00	€ 1.097,73	€ 1.097,73
S.05	Dismantling Works	CONTRACTOR			pcs	1,00	€ 878,19	€ 878,19
ELECTRICAL WORKS TOTAL								€ 168.770,65



PROJECT NAME The LEGO Group Istanbul Office Project
LOCATION Trump Tower
Sq.m (net) 720
FILE NAME MECHANICAL BOQ

DATE 21.09.2026
REV NO 1

CODE	WORK DESCRIPTION	BRAND / MARKA	PLACE / MAHAL	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(EUR)
ST	SANITARY INSTALLATION							€ 4.497,69
ST-01	KITHCEN AREA SINK Brand: It will be given by the architectural group. Models: It will be given by the architectural group. Product Code: It will be given by the architectural group. Assembly Only				pcs.	1	€ 92,18	€ 92,18
ST-02	KITHCEN AREA SINK TRAP Brand: It will be given by the architectural group. Models: It will be given by the architectural group. Product Code: It will be given by the architectural group. Assembly Only				pcs.	1	€ 92,18	€ 92,18
ST-03	KITHCEN AREA SINK FAUCET Brand: It will be given by the architectural group. Models: It will be given by the architectural group. Product Code: It will be given by the architectural group. Assembly Only				pcs.	1	€ 92,18	€ 92,18
ST-04	UNDER-COUNTER WASTE WATER PUMP Type: Under Counter Self Tank Min. Flow Rate: 4,0 m³/h Min. Pump Heat: 4 m (4,0 m³/h on flow)	Wilo, Sanihydro			pcs.	1	€ 838,24	€ 838,24
ST-05	UNDER COUNTER GREASE SEPARATOR Type:Grease separator easyclean free undersink ns 0,7	Kessel			pcs.	1	€ 1.161,88	€ 1.161,88
ST-06	PPRC PIPE (CLEAN WATER INSTALLATION) Ø25 Fittings Cost	Hakan, Firat			m %	20 50	€ 7,86 € 7,86	€ 157,23 € 78,62
ST-07	PPRC PIPE (WASTE WATER INSTALLATION) Ø50 Fittings Cost	Hakan, Firat			m %	26 50	€ 15,79 € 15,79	€ 410,42 € 205,21
ST-08	RUBBER PIPE INSULATION Insulation Of Clean Water Installation Cold Water Pipes Ø25 - DN20 (1½") - 13mm rubber foam Fittings Cost	Izocam, Ode			m %	20 25	€ 7,32 € 7,32	€ 146,32 € 36,58
ST-09	BALL VALVE DN20 Supply, installation, and commissioning of PN16 full bore ball valve with TSE quality certification, operated manually by a sphere ensuring leak-proof flow, with a body made of brass according to the fluid's pressure and temperature, a stem made of polished bronze or stainless steel, a valve disc and seat ring, threaded or flanged type, and delivered in working condition	Duyar, Ayvaz			pcs.	1	€ 34,62	€ 34,62
ST-10	SOLENOID VALVE DN20 24V	SMS Tork, Callefi			pcs.	1	€ 148,18	€ 148,18
ST-11	ELECTRIC WATER HEATER (EWH-01) Type: Under Counter Storage Capacity: 30 lt On Safety Valve	Ariston, Baymak			pcs.	1	€ 607,05	€ 607,05
ST-12	DISMANTLING OF EXISTING SANITARY SYSTEM The works include dismantling the existing sanitary piping sections as indicated in the project and stacking them on the site				pcs.	1	€ 248,00	€ 248,00
ST-13	TESTING AND COMMISSIONING Execution, pressure testing under specified conditions, and commissioning of clean and wastewater installations as indicated in the project				Set	1	€ 148,80	€ 148,80
IST-01	HEATING AND COOLING SYSTEM - FANCOIL SYSTEM							€ 91.633,00
IST-01	STEEL PIPE WITH ANTIRUST (HEATING AND COOLING INSTALLATION) Compliant With Regulation (TS 301/3) DN20 (¾") DN25 (1") DN32 (1¼") DN40 (1½") DN50 (2") DN65 (2½") Fittings Cost	Borusan, Çayirova			m m m m m m %	261 216 152 26 77 42 50	€ 18,04 € 19,22 € 23,56 € 26,04 € 32,24 € 37,20 € 37,20	€ 4.708,96 € 4.151,52 € 3.581,12 € 677,04 € 2.482,48 € 1.562,40 € 8.581,76
IST-02	RUBBER PIPE INSULATION DN20 - 19 mm. With Rubber Based Prefabricated Pipe DN25 - 19 mm. With Rubber Based Prefabricated Pipe DN32 - 19 mm. With Rubber Based Prefabricated Pipe DN40 - 19 mm. With Rubber Based Prefabricated Pipe DN50 - 19 mm. With Rubber Based Prefabricated Pipe DN65 - 19 mm. With Rubber Based Prefabricated Pipe Fittings Cost	Ode, Izocam			m m m m m m %	261 216 152 26 77 42 25	€ 6,94 € 7,19 € 7,38 € 7,44 € 7,56 € 7,69 € 7,69	€ 1.812,38 € 1.553,47 € 1.121,46 € 193,44 € 582,43 € 322,90 € 1.396,52
IST-03	BALL VALVE DN20 (¾") DN25 (1")	Duyar, Ayvaz			pcs. pcs.	112 64	€ 36,11 € 41,70	€ 4.043,96 € 2.669,09
IST-04	STRAINER DN20 (¾") DN25 (1")	Duyar, Ayvaz			pcs. pcs.	37 22	€ 36,02 € 41,07	€ 1.332,81 € 903,51
IST-05	COMBINED DYNAMIC CONTROL AND BALANCING VALVE WITH Supply and installation of Pressure Independent Control Valve (PICV) complete with 0-10V modulating actuator, dynamic flow limiter, differential pressure controller. DN20 (¾") DN25 (1")	Fresee, Danfoss			pcs. pcs.	37 22	€ 106,64 € 161,20	€ 3.945,68 € 3.546,40
IST-08	AUTOMATIC AIR VENT DN20	Duyar, Callefi			pcs.	59	€ 30,88	€ 1.821,68
IST-07	COMBINED GAUGES	Pakkens TE						



PROJECT NAME The LEGO Group Istanbul Office Project
LOCATION Trump Tower
Sq m (net) 720
FILE NAME MECHANICAL BOQ

DATE 21.09.2026
REV NO 1

CODE	WORK DESCRIPTION	BRAND / MARKA	PLACE / MAHAL	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(EUR)
	Thermomanometers are combined measurement instruments that consist of Bourdon tube pressure gauges and bimetal thermometers. That model, is designed for fitting them directly into the systems where the end-user can read both system's pressure and its temperature.							
	0...120°C & 0...10 Bar with display				pcs.	59	€ 36,58	€ 2.158,22
IST-06	FLEXIBLE CONNECTION HOSE (INSULATED) The length of each hose will be a maximum of 50cm.	Kayse, Ayvaz						
	DN20 (¾")				pcs.	62	€ 34,62	€ 2.146,52
	DN25 (1")				pcs.	56	€ 35,58	€ 1.992,56
IST-09	CONCEALED CEILING TYPE FAN COIL TWO PIPES Newly procured devices will be selected according to the office environment and will be submitted to the administration for approval. No purchases or installations will be made without approval from the administration.	Daikin, Alarko Carrier						
IST-09.01	FCU (FWE08FF) MEDIUM STATIC PRESSURE CONCEALED CEILING TYPE FAN-COIL No purchases or installations will be made without approval from the administration. Total Min. Cooling Capacity: 1,98 kW (Regime: 7-12°C, Return Air: 24°C) Sensible Cooling Capacity: 1,71 kW (Regime: 7-12°C, Return Air: 24°C) Air Flow Rate : 400 m³/h Highest Sound Output Power at the Selected Fan Speed: 49 db(A) Highest Sound Pressure at the Selected Fan Speed: 35 db(A) External Static Pressure: 60 Pa Type: 2 Pipe, Middle Static Pressure, Concealed Ceiling Type Fan-Coil	Daikin, Alarko Carrier			pcs.	1	€ 781,20	€ 781,20
IST-10	CONCEALED CEILING TYPE FAN COIL FOUR PIPES Newly procured devices will be selected according to the office environment and will be submitted to the administration for approval. No purchases or installations will be made without approval from the administration.	Daikin, Alarko Carrier						
IST-10.01	FCU (FWE24FF) MEDIUM STATIC PRESSURE CONCEALED CEILING TYPE No purchases or installations will be made without approval from the administration. Sensible Cooling Capacity: 4,67 kW (Regime: 7-12°C, Return Air: 24°C) Total Min. Heating Capacity: 9,53 kW (Regime: 7-12°C, Return Air: 24°C) Air Flow Rate : 1063 m³/h External Static Pressure: 60 Pa Highest Sound Output Power at the Selected Fan Speed: 57 db(A) Highest Sound Pressure at the Selected Fan Speed: 43 db(A) Type: 4 Pipe, Middle Static Pressure, Concealed Ceiling Type Fan-Coil	Daikin, Alarko Carrier			pcs.	2	€ 1.066,40	€ 2.132,80
IST-10.02	FCU (FWE20FF) MEDIUM STATIC PRESSURE CONCEALED CEILING TYPE No purchases or installations will be made without approval from the administration. Sensible Cooling Capacity: 4,10 kW (Regime: 7-12°C, Return Air: 24°C) Total Min. Heating Capacity: 8,61 kW (Regime: 7-12°C, Return Air: 24°C) Air Flow Rate : 900 m³/h External Static Pressure: 60 Pa Highest Sound Output Power at the Selected Fan Speed: 54 db(A) Highest Sound Pressure at the Selected Fan Speed: 40 db(A) Type: 4 Pipe, Middle Static Pressure, Concealed Ceiling Type Fan-Coil	Daikin, Alarko Carrier			pcs.	12	€ 1.023,00	€ 12.276,00
IST-10.03	FCU (FWE16FF) MEDIUM STATIC PRESSURE CONCEALED CEILING TYPE No purchases or installations will be made without approval from the administration. Sensible Cooling Capacity: 3,60 kW (Regime: 7-12°C, Return Air: 24°C) Total Min. Heating Capacity: 7,70 kW (Regime: 7-12°C, Return Air: 24°C) Air Flow Rate : 967 m³/h External Static Pressure: 60 Pa Highest Sound Output Power at the Selected Fan Speed: 58 db(A) Highest Sound Pressure at the Selected Fan Speed: 44 db(A) Type: 4 Pipe, Middle Static Pressure, Concealed Ceiling Type Fan-Coil	Daikin, Alarko Carrier			pcs.	7	€ 1.004,40	€ 7.030,80
IST-10.04	FCU (FWE08FF) MEDIUM STATIC PRESSURE CONCEALED CEILING TYPE No purchases or installations will be made without approval from the administration. Sensible Cooling Capacity: 1,71 kW (Regime: 7-12°C, Return Air: 24°C) Total Min. Heating Capacity: 3,68 kW (Regime: 7-12°C, Return Air: 24°C) Air Flow Rate : 394 m³/h External Static Pressure: 60 Pa Highest Sound Output Power at the Selected Fan Speed: 49 db(A) Highest Sound Pressure at the Selected Fan Speed: 35 db(A) Type: 4 Pipe, Middle Static Pressure, Concealed Ceiling Type Fan-Coil	Daikin, Alarko Carrier			pcs.	3	€ 837,00	€ 2.511,00
IST-10.05	FCU (FWE06FF) MEDIUM STATIC PRESSURE CONCEALED CEILING TYPE No purchases or installations will be made without approval from the administration. Sensible Cooling Capacity: 1,46 kW (Regime: 7-12°C, Return Air: 24°C) Total Min. Heating Capacity: 2,70 kW (Regime: 7-12°C, Return Air: 24°C) Air Flow Rate : 370 m³/h External Static Pressure: 60 Pa Highest Sound Output Power at the Selected Fan Speed: 49 db(A) Highest Sound Pressure at the Selected Fan Speed: 35 db(A) Type: 4 Pipe, Middle Static Pressure, Concealed Ceiling Type Fan-Coil	Daikin, Alarko Carrier			pcs.	4	€ 793,60	€ 3.174,40
IST-10.05	FCU (FWE04FF) MEDIUM STATIC PRESSURE CONCEALED CEILING TYPE No purchases or installations will be made without approval from the administration. Sensible Cooling Capacity: 0,80 kW (Regime: 7-12°C, Return Air: 24°C) Total Min. Heating Capacity: 1,87 kW (Regime: 7-12°C, Return Air: 24°C) Air Flow Rate : 215 m³/h External Static Pressure: 60 Pa Highest Sound Output Power at the Selected Fan Speed: 46 db(A) Highest Sound Pressure at the Selected Fan Speed: 32 db(A) Type: 4 Pipe, Middle Static Pressure, Concealed Ceiling Type Fan-Coil	Daikin, Alarko Carrier			pcs.	1	€ 669,60	€ 669,60
IST-11	U-PVC PIPE (FCU DRAINAGE LINE)	Pimtaş						
	Ø25				m	51	€ 8,31	€ 423,71
	Ø32				m	16	€ 8,56	€ 136,90
	Ø40				m	48	€ 8,62	€ 413,66
	Ø50				m	31	€ 8,66	€ 268,31



PROJECT NAME The LEGO Group Istanbul Office Project
LOCATION Trump Tower
Sqm (net) 720
FILE NAME MECHANICAL BOQ

DATE 21.09.2026
REV NO 1

CODE	WORK DESCRIPTION	BRAND / MARKA	PLACE / MAHAL	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(EUR)
	Fittings Cost				%	50		€ 621,29
IST-12	RUBBER PIPE INSULATION	Izocam, Ode						
	Insulation Of Drainage Water Pipes							
	Ø25 - 19 mm. With Rubber Based Prefabricated Pipe				m	51	€ 6,70	€ 341,50
	Ø32 - 19 mm. With Rubber Based Prefabricated Pipe				m	16	€ 6,76	€ 108,13
	Ø40 - 19 mm. With Rubber Based Prefabricated Pipe				m	48	€ 6,84	€ 328,55
	Ø50 - 19 mm. With Rubber Based Prefabricated Pipe				m	31	€ 7,19	€ 222,95
	Fittings Cost				%	25		€ 250,28
IST-12	SYSTEM FLUSHING AND CHEMICAL CLEANING	Daikin, Alarko Carrier			pcs.	1	€ 706,80	€ 706,80
	Chemical cleaning shall be performed to remove oil, grease, rust, and other residues from the piping system. Cleaning chemicals shall be approved by the manufacturer, and the system shall be flushed with clean water after the process							
ST-13	DISMANTLING OF EXISTING HEATING AND COOLING SYSTEM				pcs.	1	€ 1.599,60	€ 1.599,60
	The works include dismantling the existing heating and cooling piping sections as indicated in the project and stacking them on the site							
							€ 0,00	€ 0,00
IST-14	TESTING AND COMMISSIONING	Daikin, Alarko Carrier			pcs.	1	€ 347,20	€ 347,20
	Testing, flushing, balancing, and commissioning of the mechanical installation shall be carried out in accordance with the project specifications and manufacturer's instructions.							
HT	VENTILATION INSTALLATION							€ 44.181,13
HT-01	GALVANIZED AIR DUCT	Cepik Metal, Oray Mekanik						
	• Air ducts shall be manufactured from galvanized steel sheets in accordance with SMACNA, DW 142-143, and TÜV standards in automated facilities. • All longitudinal seams shall be produced using machines specially developed for these operations. • It is mandatory that all ducts and fittings are factory-fabricated, meaning they shall be cut and formed in computer-controlled (CAM) machines in a factory. • On-site fabrication of ducts or fittings using manual methods such as bending machines will not be accepted. • Air ducts shall be manufactured to be impact-resistant and airtight. • Ducts, elbows, and all branches shall comply with DIN 24190. • All duct parts, elbows, and branches shall be optimally designed for aerodynamic and acoustic performance and assembled precisely. • Duct sections shall be connected using galvanized "SB" profile flanges selected according to duct dimensions. • These flanges shall be spot welded to the duct sections, and all welded points shall be coated with galvanized paint. • Gaskets used between flanges shall be of a type that does not lose elasticity. • Seam locking methods shall not be used for connecting duct parts. • Steel profile diagonal and circumferential stiffeners shall be used where necessary in duct fabrication. • All hangers and mounting materials shall be galvanized. • All materials used shall comply with DIN 4102 Class A2. • All hangers and fixing elements shall be anchored to the building concrete							
	Made of 0.60 mm thick sheet metal, unpainted, with the widest side up to 599 mm				m²	178	€ 47,99	€ 8.541,86
	Brand: Production							
HT-02	OVAL AIR DUCT	Cepik Metal, Oray Mekanik						
	All ducts will be manufactured as painted. RAL code will be given by the architectural group. Oval supply air ducts will be insulated from the inside with 13 mm thick rubber foam.							
	605x200				m	34	€ 80,60	€ 2.740,40
	455x200				m	55	€ 70,68	€ 3.887,40
	Oval Duct Special Part Price (All equipment such as elbows, reducers, TE parts will be evaluated in this item.)				%	80		€ 5.302,24
HT-03	ELASTOMERIC RUBBER FOAM DUCT INSULATION	Izocam, Ode						
	13 mm thick rubber foam sheet insulation (Internal insulation of oval air ducts)				m	89	€ 19,22	€ 1.710,58
	19 mm thick rubber foam sheet insulation (External insulation of rectangular ducts)				m²	178	€ 17,11	€ 3.045,94
HT-04	VOLUME DAMPER	MKS, HTK, Elektrotechnik						
	150x150 mm				pcs.	10	€ 51,03	€ 510,26
	200x150 mm				pcs.	5	€ 52,26	€ 261,31
	200x200 mm				pcs.	1	€ 53,91	€ 53,91
HT-05	CAV BOX	MKS, HTK, Elektrotechnik						
	150x150 mm				pcs.	6	€ 105,90	€ 635,43
	200x200 mm				pcs.	1	€ 118,10	€ 118,10
HT-06	FRAMELESS SLOT DIFFUSER	MKS, HTK, Elektrotechnik						
	All slots will be manufactured as painted. RAL code will be given by the architectural (Plenum boxes shall be insulated internally with 9 mm acoustic insulation and externally with 13 mm elastomeric rubber insulation)							
	2-Slot Diffuser 1000 mm With Plenum Box				pcs.	2	€ 118,17	€ 236,34
	2-Slot Diffuser 1000 mm With Free Intake				pcs.	1	€ 70,68	€ 70,68
	2-Slot Diffuser 1500 mm With Plenum Box				pcs.	1	€ 177,26	€ 177,26
	2-Slot Diffuser 1500 mm With Free Intake				pcs.	1	€ 106,02	€ 106,02
	2-Slot Diffuser 2000 mm With Plenum Box				pcs.	2	€ 236,34	€ 472,69
	2-Slot Diffuser 2000 mm With Free Intake				pcs.	2	€ 141,36	€ 282,72
	2-Slot Diffuser 3500 mm With Plenum Box				pcs.	1	€ 413,60	€ 413,60
	2-Slot Diffuser 3500 mm With Free Intake				pcs.	1	€ 247,38	€ 247,38
	2-Slot Diffuser 4000 mm With Plenum Box				pcs.	1	€ 472,69	€ 472,69
	2-Slot Diffuser 4000 mm With Free Intake				pcs.	1	€ 282,72	€ 282,72
	2-Slot Diffuser 5000 mm With Plenum Box				pcs.	3	€ 590,86	€ 1.772,58
	3-Slot Diffuser 1000 mm With Plenum Box				pcs.	4	€ 142,10	€ 568,42
	3-Slot Diffuser 1000 mm With Free Intake				pcs.	2	€ 85,56	€ 171,12
	3-Slot Diffuser 1500 mm With Plenum Box				pcs.	1	€ 213,16	€ 213,16
	3-Slot Diffuser 1500 mm With Free Intake				pcs.	1	€ 128,34	€ 128,34
	3-Slot Diffuser 2000 mm With Plenum Box				pcs.	1	€ 284,21	€ 284,21
	3-Slot Diffuser 2000 mm With Free Intake				pcs.	2	€ 171,12	€ 342,24
	3-Slot Diffuser 2500 mm With Plenum Box				pcs.	1	€ 355,26	€ 355,26
	3-Slot Diffuser 3000 mm With Free Intake				pcs.	1	€ 256,68	€ 256,68
	3-Slot Diffuser 5500 mm With Plenum Box				pcs.	1	€ 781,57	€ 781,57
	3-Slot Diffuser 5500 mm With Free Intake				pcs.	1	€ 470,58	€ 470,58



PROJECT NAME The LEGO Group Istanbul Office Project
LOCATION Trump Tower
Sq m (net) 720
FILE NAME MECHANICAL BOQ

DATE 21.09.2026
REV NO 1

CODE	WORK DESCRIPTION	BRAND / MARKA	PLACE / MAHAL	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(EUR)
HT-07	DOUBLE DEFLECTION GRILLE All grille will be manufactured as painted. RAL code will be given by the	MKS, HTK, Elektroteknik						
	200x100 mm				pcs.	1	€ 43,07	€ 43,07
	400x150 mm				pcs.	24	€ 54,84	€ 1.316,16
HT-08	LINEAR GRILLE All grille will be manufactured as painted. RAL code will be given by the	MKS, HTK, Elektroteknik						
	800x200 mm				pcs.	1	€ 146,32	€ 146,32
	1500x200 mm				pcs.	10	€ 266,60	€ 2.666,00
HT-09	SQUARE DIFFUSER All diffüser will be manufactured as painted. RAL code will be given by the architectural group.	MKS, HTK, Elektroteknik						
	540x540 mm				pcs.	1	€ 163,68	€ 163,68
HT-10	INSULATED FLEXIBLE AIR DUCTS Thermally insulated, flexible, round air ducts shall be composed of double-layer tubing made of three-layer aluminium laminate with glass wool insulation of minimum 30 mm thickness between the layers. The ducts shall be manufactured from non-combustible materials classified as Class B according to DIN 4102. Flexible ducts shall have a bending radius equal to 1.2 – 2 times their outer diameter, and installation lengths shall be between 1 – 3 meters. The ducts shall comply with UL 181, NFPA 90A and 90B, and DIN 4102-A2 standards. The suspension systems for these ducts shall be implemented in accordance with SMACNA standards, with details approved by the Employer. This scope includes supply of the ducts to site, provision of all necessary sealing elements, suspension and fixing systems, and all other accessories, installation at their designated locations, commissioning, and delivery in	Flexiva Sono, AFS Sono						
	Ø152				pcs.	2	€ 11,53	€ 23,06
	Ø185				pcs.	42	€ 12,15	€ 510,38
	Ø203				pcs.	33	€ 14,63	€ 482,86
HT-11	SLEEVE Ø150 Ø180 Ø200				pcs.	3 30 19	€ 10,91 € 11,78 € 14,14	€ 32,74 € 353,40 € 268,58
HT-12	FLEXIBLE CONNECTOR FCU devices will be connected to the suction and discharge lines with bellows and vibration damping will be provided.				pcs.	30	€ 44,64	€ 1.339,20
HT-13	DISMANTLING OF EXISTING HEATING AND COOLING SYSTEM The works include dismantling the existing ventilation duct sections as indicated in				pcs.	1	€ 1.550,00	€ 1.550,00
HT-14	TEST-ADJUSTMENT-BALANCING WORKS FOR VENTILATION SYSTEM The measurement and adjustment work of the air supply duct will be carried out by a third-party company. The company must possess all necessary accreditation documents. Calibration certificates for all devices used shall be submitted to the employer. The third-party company shall declare that the values specified in the project are achieved within the tolerance range.				Set	1	€ 372,00	€ 372,00
YT	FIRE FIGHTING SYSTEM							€ 33.288,54
YT-01	SPRINKLER UPRIGHT, 68°C, K=80 Type: (Upright) Quick response Activation Temperature: 68°C K factor: 80 Connection Diameter: DN15 (½") Sprinklers with UL listing and FM approval, with brass body, operating pressure of	Tyco, Globe, Reilable			pcs.	73	€ 30,08	€ 2.196,02
YT-02	SPRINKLER PENDENT, 68°C, K=80 Tip: Concealed Type (Pendent) Quick response Activation Temperature: 68°C K factor: 80 Connection Diameter: DN15 (½") Sprinklers with UL listing and FM approval, with brass body, operating pressure of	Tyco, Globe, Reilable			pcs.	76	€ 41,81	€ 3.177,77
YT-03	SPRINKLER UPRIGHT, 79°C, K=80 (WITH PROTECTION CAGE) Type: (Upright) Quick response Activation Temperature: 79°C K factor: 80 Connection Diameter: DN15 (½") Sprinklers with UL listing and FM approval, with brass body, operating pressure of The sprinkler head shall be procured with a protection cage and installed	Tyco, Globe, Reilable			pcs.	2	€ 26,66	€ 53,32
YT-04	SPRINKLER HOOSE AND CONNECTION SET Maks. Length L=100cm. The sprinkler connection hose shall be FM approved, UL listed, or VDS certified. The hose material shall be AISI 316L stainless steel, and the braid wire material shall be AISI 304 stainless steel. The minimum pressure rating is PN16, hose diameter DN25, sprinkler connection ½" NPT, and fixed pipe connection 1" nipple. The hose length shall not exceed 100 cm. Supply of the flexible sprinkler connection hose with all materials as described above, suitable installation, and secure fastening compatible with sprinkler operation.	Kayse, Ayvaz			pcs.	76	€ 36,95	€ 2.808,35
YT-05	STEEL PIPE DN25 (1") DN32 (1¼") DN40 (1½") DN50 (2") DN65 (2½") DN80 (3") In the fire protection system, pipes DN65 (2½") and above shall be with grooved Fittings Cost	Borusan, Çayirova			m m m m m m %	302 59 27 28 34 29 50	€ 19,22 € 23,56 € 26,04 € 32,24 € 37,20 € 47,12 X	€ 5.804,44 € 1.390,04 € 703,08 € 902,72 € 1.264,80 € 1.366,48 € 5.715,78
YT-06	PIPE PAINTING WITH 2 COAST OF STAINLESS PAINT After the installation of the pipes, all dirt, mortar, and similar debris on their surfaces DN25 (1") to DN50 (2") (including the specified diameters) DN65 (2½") to DN150 (6") (including the specified diameters) Brand: DYO, ÇBS, Marshall, Polisan	Polisan, Dyo			m m	416 63	€ 2,73 € 2,73	€ 1.134,85 € 171,86



PROJECT NAME The LEGO Group Istanbul Office Project
LOCATION Trump Tower
Sqm (net) 720
FILE NAME MECHANICAL BOQ

DATE 21.09.2026
REV NO 1

CODE	WORK DESCRIPTION	BRAND / MARKA	PLACE / MAHAL	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(EUR)
YT-07	PIPE PAINTING WITH 2 COAST OF OIL PAINT	Polisan, Dyo						
	After the anti-rust application, two coats of oil-based paint are applied in the color							
	DN25 (1") to DN50 (2") (including the specified diameters)				m	416	€ 2,73	€ 1.134,85
	DN65 (2½") to DN150 (6") (including the specified diameters)				m	63	€ 2,73	€ 171,86
	Brand: DYO, ÇBS, Marshall, Polisan							
YT-08	SEISMIC PROTECTION INSTALLATION (FIRE FIGHTING SYSTEM)	Erico, Link			Set	1	€ 3.841,52	€ 3.841,52
	Seismic protection will be provided in the fire extinguishing system. The pre-							
YT-09	DISMANTLING OF EXISTING FIRE FIGHTING SYSTEM				pcs.	1	€ 1.116,00	€ 1.116,00
	The works include dismantling the existing fire piping as indicated in the project and							
YT-10	TESTING AND COMMISSIONING				Set	1	€ 334,80	€ 334,80
	Manufacture of the specified quantity and type of sprinklers in accordance							
MO	MECHANICAL AUTOMATION							€ 23.550,97
MO-01	BMS&EMS	Siemens			Set	1	€ 23.550,97	€ 23.550,97
	RDF460MB Wall Type Room Module							
	AX-WLD2-24-A Water Leak Detector, 12A Relay Output, 24V AC/DC, Audible Alarm, Max Operating Temperature 0-40°C							
	AX-WCS-EL010 Water Leak Detectors With 10-Meter Sensing Cable							
	B-BC System Controller BACnet/IP							
	Pano-DU-60120 - 600x1200x200 EAE							
	Central Bms Software & Hardware							
	Test & Commissioning (On-Site Supervision, Labeling and Commissioning							
MECHANICAL WORKS TOTAL :								€ 197.151,33
OPTIONAL MECHANICAL WORKS								
MO.1								€ 1.909,60
MO 1.1	DECORATIVE FIRE CABINET WITH GLASS DOOR	Fetaş, Dooras, Acco			Set	2	€ 954,80	€ 1.909,60
	Supply and installation of new recessed type decorative fire cabinet							€ 0,00
	2" gate valve, suitable for fire department connection. The hose length shall be 25 meters							€ 0,00
								€ 0,00
								€ 0,00
								€ 0,00

CODE	WORK DESCRIPTION	BRAND / MARKA	EXPLANATION / AÇIKLAMA	UNIT	QUANTITY	UNIT PRICE	TOTAL(TL)
A	LIGHTING WORKS						€ 81.728,08
LT-01	Linear light inbetween acoustic ceiling panels	db's Notes: Intra Lighting Kalis SDI db's Notes:		pcs	12,00	€ 898,18	€ 10.778,14
LT-02	Recessed pendant light	db's Notes: Intra Lighting Wave round C/S db's Notes:		pcs	2,00	€ 2.015,05	€ 4.030,10
LT-03	Recessed pendant light	db's Notes: Intra Lighting Lons C/S db's Notes:		pcs	2,00	€ 524,06	€ 1.048,13
LT-04	Suspended acoustic raft with integrated linear light	db's Notes: Feltouch Flat Cloud CLD350 db's Notes:		pcs	2,00	€ 642,48	€ 1.284,96
LT-05A	Suspended acoustic raft with integrated linear lights	db's Notes: Feltouch Flat Cloud CLD371 db's Notes:		pcs	6,00	€ 1.843,49	€ 11.060,93
LT-05B	Suspended acoustic raft with integrated linear lights	db's Notes: Feltouch Flat Cloud CLD371 db's Notes:		pcs	5,00	€ 1.843,49	€ 9.217,45
LT-06A	Suspended acoustic raft with integrated linear light	db's Notes: Feltouch Flat Cloud CLD310 db's Notes:		pcs	1,00	€ 578,50	€ 578,50
LT-06B	Suspended acoustic raft with integrated linear light	db's Notes: Feltouch Flat Cloud CLD310 db's Notes:		pcs	1,00	€ 578,50	€ 578,50
LT-07	Suspended acoustic raft with integrated linear light	db's Notes: Feltouch Flat Cloud CLD320 db's Notes:		pcs	1,00	€ 939,53	€ 939,53
LT-08	Suspended Pendant light	db's Notes: Feltouch Layer ML330 db's Notes:		pcs	1,00	€ 1.460,33	€ 1.460,33
LT-09	Wall light	db's Notes: Pholic Lille 18 db's Notes:		pcs	2,00	€ 818,40	€ 1.636,80
LT-10	Suspended Pendant light	db's Notes: Oblure Arch Straight db's Notes:		pcs	1,00	€ 4.038,97	€ 4.038,97
LT-11	Suspended Pendant light	db's Notes: DeVorm Split Straight Rail Pendant Orbit db's Notes:		pcs	1,00	€ 5.202,84	€ 5.202,84
LT-12	Suspended Pendant light	db's Notes: Pluscouple Radius db's Notes:		pcs	2,00	€ 348,75	€ 697,50
LT-13	Recessed downlight	db's Notes: Intra Lighting Pipes RI db's Notes:		pcs	46,00	€ 60,49	€ 2.782,64
LT-14	Suspended acoustic raft with integrated linear light	db's Notes: Feltouch Cracker Cloud db's Notes:		pcs	1,00	€ 754,86	€ 754,86
LT-15	Wall light	db's Notes: Vibia Dots Wall 4675 db's Notes:		pcs	2,00	€ 520,80	€ 1.041,60
LT-16	Suspended Can Lights	db's Notes: Intra Lighting Pipes S45 db's Notes:		pcs	52,00	€ 298,01	€ 15.496,35
LT-17	EXISTING LEGO Pendant light	-	Due to the existing lighting, only the installation has been priced in the electrical boq	pcs	1,00	€ -	€ -
LT-18	Linear profile light	db's Notes: Intra Lighting - Linear profile Ligt db's Notes:		pcs	1,00	€ 7.993,15	€ 7.993,15
LT-19	Concealed LED Strip	db's Notes: Optimum - Flex Led 10W/m db's Notes:	Please check the quantity from the joinery drawings	m	47,75	€ 22,22	€ 1.061,04
LT-20	Concealed LED Strip	db's Notes: Optimum - Flex Led 10W/m db's Notes:	Please check the quantity from the ceiling drawings	m	2,06	€ 22,22	€ 45,77
LIGHTING WORKS TOTAL							€ 81.728,08



Daima Yanınızda

PlusTech Güvenlik Sistemleri A.Ş.
Boğaziçi 2. Kısım Mh. Hoşdere Cd. Tunç Sk.
No: 1/8 Beşiktaş / İSTANBUL
Boğaziçi V.D.: 750077534
T: 444 1 481 F: 0212 672 75 36

info@plustech.com.tr | plustech.com.tr

Turnike Sistemi Teklifi

Teklif No: PT-26-07-042

MÜŞTERİ BİLGİLERİ					
Müşteri	: Time- İst	Teklif Tarihi	: 27.07.2026		
İlgili Kişi	: Salih Sözen	Geçerlilik Tarihi	: 11.08.2026		
Telefon	: 905332384864	Hazırlayan	: Serpil BAYRAM		
E-mail	: salih.sozmen@time-ist.com	E-mail	: satiste@plustech.com.tr		
NO	ÜRÜN KODU	ÜRÜN ADI	MİKTAR	BİRİM FİYAT	TUTAR
1	PTG-PG-03-90-S	Hızlı Geçiş Turnikesi, 120cm Cam Kanatlı, 90cm Geçiş Ara	2 Ad	3.000,00 €	6.000,00 €
2	PTH-TS	Teknik Servis Bedeli	1 Ad	600,00 €	600,00 €
				Ara Toplam :	6.600,00 €
				Kdv %20 :	1.320,00 €
				Genel Toplam :	7.920,00 €

This scope will be done by the Security vendor, and this security vendor will be under the GC. The scope is approximately 40K Euro.	
Amount	Type
1	Cloudlink 210 44Tb
4	Genetec Omnicast camera license Saas first year
7	Saas ACS licenses year one
1	Secure Cloud link, incl. Installation
1	Mercury LP1502 controller, incl. Installation
3	Mercury MR52 2-door controller, incl. Installation
1	Mercury MR16 I/O board for intruder alarm zones
1	Controller enclosure, incl. PSU/back-up
5	STiD Readers/doors - including lock works
2	STiD Readers/doors - for Gates/speedstiles/glass doors/tripods/out readers
5	Opening contacts ACS
2	Opening contacts IAS
3	I-Pro WV-U21350- V3LV indoor camera 2Mp
1	I-Pro WV-U21550-V3LV indoor camera 5Mp
0	Came 900mm Speedstile lane
1	Commissioning and travel



Daima Yanınızda

PlusTech Güvenlik Sistemleri A.Ş.
Boğaziçi 2. Kısım Mh. Hoşdere Cd. Tunç Sk.
No: 1/8 Beşiktaş / İSTANBUL
Boğaziçi V.D.: 750077534
T: 444 1 481 F: 0212 672 75 36

info@plustech.com.tr | plustech.com.tr

Turnike Sistemi Teklifi

Teklif No: PT-26-07-042

TEKLİF KOŞULLARI
-Teklifimize nakliye dahildir.
-Montaj ve Devreye Alma teklifimize dahildir.
-Kart okuyucu sistemi hariçtir.
-Altyapı için gerekli malzemeler (kablo, boru, kanal vb.) teklifimize dahil değildir.
-Altyapı için gerekli kazı, kırma ve kablolama işçiliği teklifimize dahil değildir.
-Tüm elektronik ürünler üretim hatalarına karşı iki yıl garanti kapsamındadır.
-Uygunsuz ortamlar (aşırı nem, sıcaklık, hatalı depolama, su baskması, gerilim düşmesi/yükselmesi, elektriksel problemler vb.), hatalı kullanım ve yetkili olmayan kişilerin müdahalesi ile oluşabilecek problemler garanti kapsamı dışındadır.
-Sistemlere UPS (kesintisiz güç kaynağı) bağlanması sistemlerin güvenliği ve elektriksel problemleri önlemek için tavsiye edilir.
-Bu teklifte belirtilen fiyatlar avans tarihindeki Ziraat Bankası Amerikan Dolan Satış Kuru üzerinden Türk Lirasına çevrilecektir.
-Ödeme Şartları: KDV'li toplam tutarın tamamı sipariş tarihinde banka havalesi ile peşin olarak ödenecektir.

PlusTech Güvenlik Sistemleri A.Ş.
Adına Teklifi Düzenleyen
Ad-Soyad / İmza

Serpil BAYRAM